

## **CHECKLIST ONCE HOOKED UP**

Ensure hitch has connected properly and locked

Connect trailer plug, Anderson plugs and camera

Ensure hitch pin in gooseneck is in place and secured

Attach breakaway cable

Fit weight distribution bars (if you use them)

Check all lights for correct operation

Check brake controller for any errors

Remove and store wheel chocks and level ramps

Ensure numberplate is secure and visible

Cover on gas heater vent fitted and secure

Final look around van ensuring all hatches and doors are closed, all services disconnected and windows are closed

Test emergency manual brakes before leaving caravan park